# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
## Office of the Executive Engineer, Dasarahalli Division
### Schedule-B

**NAME OF THE WORK:** Improvements & resaphlating road from 5th & 6th cross road kempegowda nagara & Ramachandra hospital road Bhuvaneshwari nagara in Dasarahalli ward no. 15

| Sl. No | Description of work | Unit | Qty | Rate Quoted by Contractor Sri K.T Ramesh | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Removing B.S slab of drain and stacking complete as per the direction of Engineer-in-charge of the work | sqm | 1785.42 | 50.0 | Rupees Fifty Only |
| 2 | Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work | cum | 751.00 | 130.0 | Rupees One Hundred Thirty Only |
| 3 | Refixing stone slabs of drains and pointing in CM 1:3 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. | sqm | 1785.42 | 60.0 | Rupees Sixty Only |
| 4 | Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials - Data rate approved by Chief Engineer, Dasarahalli zone | sqm | 176.58 | 1200.0 | Rupees One Thousand Two Hundred Only |

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| 5 | Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. complete as per the direction of Engineer-in-charge of the work | sqm | 485.00 | 4.0 | Rupees Four Only |
| 6 | For Grading I material construction of granular sub-base by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material . complete as per the direction of Engineer-in-charge of the work | cum | 72.75 | 1200.0 | Rupees One Thousand Two Hundred Only |
| 7 | Providing, laying, spreading and compacting stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. Complete as per specifications complete as per the direction of Engineer-in-charge of the work. | cum | 72.75 | 1300.0 | Rupees One Thousand Three Hundred Only |
| 8 | Providing and applying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of .60kg /sqm using mechanial means complete as per Specifications. complete as per the direction of Engineer-in-charge of the work | sqm | 485.00 | 26.0 | Rupees Twenty Six Only |
| 9 | Providing and applying tack coat on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface ) including cost of all materials, labour, HOM of machineries complete as per specifications. complete as per the direction of Engineer-in-charge of the work | sqm | 6380.75 | 10.0 | Rupees Ten Only |

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| 10 | Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50/75mm compacted thickness with 3.3% bitumen but excluding the cost of primer/tack coat with lead incl. cost of all materials, labour, HOM of machineries complete as per specifications with 80/100 grade bitumen using 40/60TPH capacity H.M.P with Mechanical paver Gr II (50/75mm) with 3.3% VG-30 Bitumen as per the directions of Engineer-in-charge of the work complete as per the direction of Engineer-in-charge of the work | cum | 24.25 | 4900.0 | Rupees Four Thousand Nine Hundred Only |
| 11 | Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. complete as per the direction of Engineer-in-charge of the work | sqm | 5895.75 | 3.0 | Rupees Three Only |
| 12 | Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, pre mixed with bituminous binder and filler, transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment . Rolling with smooth wheeled Vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause no 500.9 complete in all respects complete as per specifications. MORTH specification No509, using 100/120 TPH capacity H.M.P.with Mechanical paver Gr -II (30mm to 45mm) with 6% VG-Bitumen complete as per the direction of Engineer-in-charge of the work | cum | 235.83 | 6000.0 | Rupees Six Thousand Only |

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| 13 | Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. complete as per the direction of Engineer-in-charge of the work | sqm | 190.50 | 455.0 | Rupees Four Hundred Fifty Five Only |

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner